

# SAN FRANCISCO BAY AREA WATER EMERGENCY TRANSPORTATION AUTHORITY

## NORTH BAY OPERATIONS AND MAINTENANCE FACILITY – PILE RECONFIGURATION PROJECT

IFB #17-020

### ADDENDUM NO. 5

August 16, 2017

#### SCOPE

Addendum No. 5 consists of one (1) page. Addendum No. 5 includes the following:

1. Questions and Answers

This addendum has been posted on the WETA website for review by all potential bidders.

#### 1. Questions and Answers

**Q8:** Within Invitation for Bids – Volume 3 – Site Work – Specification Section 31 62 16 – Steel Pile – Part 3 Execution - 3.3 GUIDE PILE CAPS - A. there is a requirement to: Install fabricated steel cone hats on the tops of all dolphin and vessel impact piles. Cone hats shall be minimum ¼" thickness and coated to match piles. It should be noted that the Contract Plans – Sheet No. SM-101 – Sheet 2 of 2 includes the requirement to: Install Sealite SL60 Blue Navigation Light with Bird Spike on Pile Hat.

We have been advised by the Sealite Navigation Light supplier that mounting for these lights should be on a flat surface, not a "cone."

Please provide a detail of the mounting of these Sealite Navigation Lights on the "pile hats."

**A8:** The contractor can grind off the end of the steel cone and weld a flat plate to provide the flat surface required for mounting of the navigation lights. Other equivalent solutions will be considered by WETA.

**Q9:** Please confirm that the requirement to "Install fabricated steel cone hats on the tops of all dolphin and vessel impact piles." refers to only the 3 new pile being installed in conjunction with this contract, and not to all existing pile within the NBOMF.

**A9:** WETA confirms that the cone hats are only to be mounted on the three (3) new piles.

#### ACKNOWLEDGMENT BY BIDDER

Each bidder is required to acknowledge receipt of all Addenda, including this Addendum No. 5 as specified in the IFB Instructions to Bidders.

#### ISSUED BY

  
\_\_\_\_\_  
Chad Mason  
Project Manager

8/16/17  
\_\_\_\_\_  
Date